


## PLANNING AND DEVELOPMENT DEPARTMENT CASE REPORT

**Case Number:** RZR2024-00032  
**Current Zoning:** RA-200 (Agriculture-Residence District)  
**Request:** Rezoning to R-60 (Single-Family Residence District)  
**Additional Requests:** Variance and Waiver  
**Address:** 2287 Rabbit Hill Circle  
**Map Number:** R7018 002  
**Site Area:** 23.13 acres  
**Units:** 64  
**Proposed Development:** Single-Family Detached Subdivision  
**Commission District:** District 4 – Commissioner Holtkamp  
**Future Development Type:** Neighborhood Traditional

**Staff Recommendation:** APPROVAL WITH CONDITIONS



**Applicant:** Inline Communities, LLC  
c/o Mahaffey Pickens Tucker, LLP  
1550 North Brown Road, Suite 125  
Lawrenceville, GA 30043

**Owners:** Clyde H. Nichols  
Carlton Roger Dills  
3180 Old Peachtree Road  
Dacula, GA 30019

**Contact:** Shane Lanham

**Contact Phone:** 770.232.0000

## Zoning History


The subject site is zoned RA-200 (Agriculture-Residence District). No previous zoning cases are on file for this property.

## Existing Site Condition

The subject property is a 23.13-acre parcel located along Rabbit Hill Circle, east of its intersection with Nichols Road. There is a single-family residence and accessory buildings on the site accessed by a driveway from Rabbit Hill Circle. The site is wooded with a stream running through the northern portion of the property. The front of the site is relatively flat while the terrain of the rear half of the site falls approximately 80 feet towards the stream. Rabbit Hill Circle is a dead-end street that is not designed to County standards and lacks a sidewalk on either side. The nearest Gwinnett County Transit stop is approximately 6.3 miles from the subject property.

## Surrounding Use and Zoning

The site is surrounded by existing residential uses and undeveloped land. To the east and west along Rabbit Hill Circle are single-family residences on large lots, and undeveloped parcels. Farther to the east, is the rights-of-way for the future Sugarloaf Parkway extension. The site abuts Ivey Chase to the north, a single-family detached subdivision with a density of 2.27 units per acre. To the south across Rabbit Hill Circle is a parcel that was rezoned in 2023 for a single-family detached subdivision with a density of 3.59 units per acre. Nichols Glen, a subdivision with a density of 4.2 units per acre, is located to the southwest across Nichols Road. The following is a summary of surrounding uses and zoning:



Location	Land Use	Zoning	Density
Proposed	Single-Family Residential	R-60	2.76 units per acre
North	Single-Family Residential	R-100 MOD	2.27 units per acre
East	Single-Family Residential Undeveloped	RA-200 RA-200	0.50 units per acre N/A
South	Single-Family Residential Single-Family Residential	R-60 RA-200	3.59 units per acre 1.00 units per acre
West	Single-Family Residential Undeveloped	RA-200 RA-200	0.20 units per acre N/A

## Project Summary

The applicant requests a rezoning of a 23.13-acre parcel from RA-200 to R-60 for a single-family detached subdivision including:

- 64 single-family detached residences on lots ranging in size from 7,472 square feet to 13,401 square feet, yielding a density of 2.76 units per acre.
- Residences with a minimum heated floor area of 1,800 square feet with front-loaded, two-car garages.
- Exterior building materials of brick, stacked stone, fiber cement shake, and/or siding.
- A total of 3.35 acres of open space located in the front and rear of the development.
- A total of 1.54 acres of usable open space including a pocket park with benches along Rabbit Hill Circle, and a mulched trail and seating areas facing the stormwater facility in the rear.
- A 40-foot-wide street frontage setback with 10-foot-wide landscape strip along Rabbit Hill Circle.
- One full-access entrance along Rabbit Hill Circle.
- 27-foot-wide internal streets within 50-foot-wide rights-of-way.
- A five-foot-wide sidewalk along only the improved portion of Rabbit Hill Circle, and five-foot-wide sidewalks on both sides of the proposed internal streets.
- One stormwater management facility in the rear of the development.

## Zoning and Development Standards

The applicant is requesting a rezoning to R-60 for a single-family detached subdivision. The following is a summary of applicable development standards from the Unified Development Ordinance (UDO):

Standard	Required	Proposed	Meets Standard?
Density	Maximum 4.0 units/acre	2.76 units/acre	YES
Lot Size	Minimum 7,200 square feet	Minimum 7,472 square feet	YES
Lot Width	Minimum 60'	>60 feet	YES
Lot Coverage	Maximum 60%	<60%	YES
Front Yard Setback	Minimum 15'	15' 10' (corner lots)	YES NO*
Rear Yard Setback	Minimum 20'	20'	YES
Side Yard Setback	Minimum 5'	5'	YES
Building Height	Maximum 35'	<35'	YES
Open Space	Minimum 10% or 2.31 acres	14.5% or 3.35 acres	YES

Usable Open Space	Minimum 5% or 1.16 acres	6.7% or 1.54 acres	YES
Street Frontage Setback	Minimum 40' 10' wide landscape strip	Minimum 40' 10' wide landscape strip	YES
Sidewalks	Along entire road frontage	Along partial road frontage	NO**

\* The applicant is requesting a variance from the required front setback on corner lots.

\*\* The applicant is requesting a waiver from the external sidewalk requirement.

### Variance Request

In addition to the rezoning request, the applicant is seeking a variance from the following provision of Title II of the UDO:

1. Table 210-120 Dimensional Standards for Base Residential Zoning Districts

**The minimum front setback for R-60 zoned lots is 15 feet.**

The applicant is requesting a variance to allow a reduced front yard setback of 10 feet for corner lots, only for the yard located between the side façade of the home and the street. This variance would apply to three lots within the development (Lots 41, 42, and 53).

### Waiver Request

In addition to the rezoning request, the applicant is seeking a waiver from the following provision of Title III of the UDO:

1. Section 360-90.3 A. Sidewalk design and construction standards

**A. Width. Sidewalks shall be at least 4 feet wide on new internal subdivision streets and at least 5 feet wide on abutting external streets.**

The applicant is requesting to eliminate the required sidewalks along the Rabbit Hill Circle frontage to the east of the subdivision entrance.

### Public Participation

The applicant held a community meeting for the development on May 30, 2024 at Rabbit Hill Park in Dacula. There were twelve community members in attendance, who raised questions and concerns regarding rental restrictions, utilities, sidewalks, and proposed home price points. The applicant responded to these concerns and is requesting a 5% maximum rental restriction on the community. The public participation plan and report are shown in Exhibit H.

### Internal and External Agency Review

In addition to these Development Standards, the applicant must meet all other UDO requirements related to infrastructure improvements. Internal and External agency review comments are attached (Exhibit I). Standard site and infrastructure improvements will also be required related to stormwater, transportation, water, and sewer utilities. Recommended improvements not already required by the UDO have been added as staff recommended conditions.



## Staff Analysis

**Rezoning Request Analysis:** According to the UDO, if a proposed amendment is for the rezoning of property and involves a change in zoning classification, the Department shall evaluate the request and make a recommendation with respect to the standards governing exercise of zoning power as defined in Section 270-20.6. After this evaluation, staff makes the following findings based on the standards from the UDO:

**A. Whether a proposed rezoning will permit a use that is suitable in view of the use and development of adjacent and nearby property.**

The surrounding area is entirely single-family detached residential, with older residences on large parcels along Rabbit Hill Circle and newer residences within subdivisions. The proposed single-family detached subdivision is suitable in view of the use and development of adjacent and nearby properties, as it creates a transition in density between the denser R-60 zoned future subdivision to the south and the less dense R-100 MOD zoned Ivey Chase subdivision to the north.

**B. Whether a proposed rezoning will adversely affect the existing use or usability of adjacent or nearby property.**

The proposed use is consistent with the character and development patterns of nearby existing and approved residential subdivisions. As such, no adverse impacts on the existing use or usability of adjacent or nearby property are anticipated.

**C. Whether the property to be affected by a proposed rezoning has a reasonable economic use as currently zoned.**

The property has reasonable economic use as currently zoned.

**D. Whether the proposed rezoning will result in a use which will or could cause an excessive or burdensome use of existing streets, transportation facilities, utilities, or schools.**


An increase in impacts on public facilities is anticipated in the form of traffic, utility demand, and stormwater runoff; however, these impacts would be mitigated with appropriate conditions, site development requirements, and planning. The traffic impact study submitted for the development estimated that the subdivision would generate 51 morning peak hour and 67 evening peak hour trips within a 24-hour period and have minimal impacts on traffic operations. The study recommended upgrading Rabbit Hill Circle to current standards between Nichols Road and the site entrance. An increased impact is anticipated on school enrollment. Agency review comments concerning any potential improvements related to this request are attached (Exhibit I).

**E. Whether the proposed rezoning is in conformity with the policy and intent of the Unified Plan and Future Development Map; and**

The Unified Plan's Future Development Map indicates "Neighborhood Traditional" for the subject property, which envisions single-family residential development with a density of up to 1.7 units per acre in areas that lack sewer service. Since sewer is available to this site, the "Neighborhood Traditional+" future development type which allows a greater density and a mix

of housing types should apply instead. This development type encourages residences to be built with front porches, modest setbacks, and side or alley loaded garages to promote a pedestrian-friendly environment. Street and sidewalk connectivity are also encouraged as practicable.

The proposed rezoning is for R-60, a recommended zoning district in the "Neighborhood Traditional+" future development type. Although the proposed density is less than targeted for this development type, it is consistent with the surrounding area. The development has connected streets and sidewalks; however, homes would be entirely front-loaded with small front stoops. The proposed rezoning is in general conformity with the policy and intent of the Unified Plan and Future Development Map.



**F. Whether there are other existing or changing conditions affecting the use and development of the property which give supporting grounds for either approval or disapproval of the proposed rezoning.**

There are no other conditions giving support for approval or disapproval of the proposal.

**Variance Request Analysis:** The standards for granting variances are outlined in Section 270-90.7 of the UDO. Staff makes the following findings related to the variance request:

The applicant requests a variance to reduce the setback on three corner lots along one frontage from 15 feet to 10 feet. This reduction in the front setback is only for the portion of the residence that does not function as the front façade. The proposed lot sizes and density, including the reduced setback, are compatible with the nearby single-family residences and meet the intent of the UDO requirements for the R-60 zoning district.

**Waiver Request Analysis:** When considering waivers from Title III of the UDO, staff is required to review whether an undue hardship may result from strict compliance with the regulations and that approval would not adversely affect the general public welfare or nullify the intent of the Development Regulations. In addition, there must be a determination that there are unusual topographical or other exceptional conditions. Staff makes the following findings related to the waiver request:

The applicant requests a waiver to eliminate the required five-foot-wide sidewalk along the Rabbit Hill Circle frontage to the east of the proposed subdivision entrance. The portion of Rabbit Hill Circle beyond the entrance is not required to be improved as part of the development. However, should development occur on the properties to the east, Rabbit Hill Circle would have to be improved and an existing sidewalk to connect to that development would be warranted. Approval of the requested waiver would adversely affect the general public welfare and nullify the intent of the Development Regulations.

### **Staff Recommendation**

Based on the staff's evaluation of the request and the standards governing the exercise of zoning power, the Department of Planning and Development recommends **APPROVAL WITH CONDITIONS** of the rezoning request.

In addition, staff recommends **APPROVAL** of the following variance request:

1. To allow a reduced front setback to ten feet on the street side of corner lots.

In addition, staff recommends **DENIAL** of the following waiver request:

1. To eliminate the required sidewalks along the Rabbit Hill Circle frontage.

### **Staff Recommended Conditions**

Approval as R-60 (Single-Family Residence District) subject to the following conditions:

1. The development shall be limited to single-family detached dwellings and accessory uses and structures, not exceeding 64 units.
2. The proposed development shall be constructed in general conformance with Exhibit B: Site Plan dated received May 17, 2024, and Exhibit C: Elevations dated received May 17, 2024, by the Department of Planning and Development, with revisions required by conditions and the Unified Development Ordinance, subject to the review and approval of the Department of Planning and Development.
3. The minimum heated floor area of each dwelling shall be 1,800 square feet.
4. Usable open space shall be designed as active or passive recreational space and dispersed so that all lots are within 500 feet of usable open space. Usable open space shall be located outside of stream buffers and impervious setbacks and shall be subject to the review and approval of the Department of Planning and Development.

5. The entire property frontage of Rabbit Hill Circle shall be upgraded to minimum standards for "local road", subject to the review and approval of the Gwinnett County Department of Transportation.
6. The intersection of Rabbit Hill Circle and Nichols Road shall be redesigned and constructed as a three-way stop-controlled intersection or realigned as a "T" intersection, subject to the review and approval of the Gwinnett County Department of Transportation.
7. A five-foot-wide sidewalk shall be provided along the entire Rabbit Hill Circle property frontage, subject to the review and approval of the Gwinnett County Department of Transportation.
8. Stormwater BMP facilities that are not designed as an amenity shall be screened from view of adjoining properties and rights-of-way by landscaping and/or decorative fencing that is in compliance with the Gwinnett County Stormwater Management Manual, subject to review and approval by the Department of Planning and Development.
9. Natural vegetation shall remain on the property until the issuance of a development permit.
10. All grassed areas within lots and usable open space shall be sodded.

**Exhibits:**

- A. Site Visit Photos
- B. Site Plan
- C. Building Elevations
- D. Letter of Intent and Applicant's Response to Standards
- E. Application and Disclosure of Campaign Contributions
- F. DWR Sewer Capacity Certification Letter
- G. Traffic Impact Study
- H. Public Participation Plan and Report
- I. Internal and External Agency Review Comments
- J. Maps



**Exhibit A: Site Visit Photos**



View of interior of the site



View of existing residence on the site





View of Rabbit Hill Circle, subject site on left




View of residence to the south across Rabbit Hill Circle



**Exhibit B: Site Plan**

**[attached]**






LOT DATA TABLE			
LOT NUMBER	LOT AREA (SF)	MAX ALLOWABLE LOT COVERAGE (%)	PROVIDED LOT COVERAGE (%)
1	7750	60	LESS THAN 60
2	7750	60	LESS THAN 60
3	7750	60	LESS THAN 60
4	7750	60	LESS THAN 60
5	7780	60	LESS THAN 60
6	7751	60	LESS THAN 60
7	7751	60	LESS THAN 60
8	7751	60	LESS THAN 60
9	7751	60	LESS THAN 60
10	7732	60	LESS THAN 60
11	7750	60	LESS THAN 60
12	7750	60	LESS THAN 60
13	7750	60	LESS THAN 60
14	7928	60	LESS THAN 60
15	9131	60	LESS THAN 60
16	9333	60	LESS THAN 60
17	9090	60	LESS THAN 60
18	8027	60	LESS THAN 60
19	9029	60	LESS THAN 60
20	8219	60	LESS THAN 60
21	11886	60	LESS THAN 60
22	7887	60	LESS THAN 60
23	7887	60	LESS THAN 60
24	8038	60	LESS THAN 60
25	9006	60	LESS THAN 60
26	8519	60	LESS THAN 60
27	7887	60	LESS THAN 60
28	7887	60	LESS THAN 60
29	8480	60	LESS THAN 60
30	7750	60	LESS THAN 60
31	7750	60	LESS THAN 60
32	7750	60	LESS THAN 60
33	7500	60	LESS THAN 60
34	7730	60	LESS THAN 60
35	8027	60	LESS THAN 60
36	11123	60	LESS THAN 60
37	10030	60	LESS THAN 60
38	8244	60	LESS THAN 60
39	8476	60	LESS THAN 60
40	7472	60	LESS THAN 60
41	8724	60	LESS THAN 60
42	11803	60	LESS THAN 60
43	9340	60	LESS THAN 60
44	9391	60	LESS THAN 60
45	9441	60	LESS THAN 60
46	9492	60	LESS THAN 60
47	9543	60	LESS THAN 60
48	9594	60	LESS THAN 60
49	9645	60	LESS THAN 60
50	9696	60	LESS THAN 60
51	9747	60	LESS THAN 60
52	13451	60	LESS THAN 60
53	8242	60	LESS THAN 60
54	7750	60	LESS THAN 60
55	7877	60	LESS THAN 60
56	9844	60	LESS THAN 60
57	9406	60	LESS THAN 60
58	9546	60	LESS THAN 60
59	11889	60	LESS THAN 60
60	9229	60	LESS THAN 60
61	9244	60	LESS THAN 60
62	9838	60	LESS THAN 60
63	8437	60	LESS THAN 60
64	12483	60	LESS THAN 60



SITE DATA	
TOTAL LAND AREA	25.132 ACRES
PARCEL ID (FPM)	7048-000
<b>ZONING</b>	
EXISTING ZONING	RA200
PROPOSED ZONING	R60
ZONING JURISDICTION	GWINNETT COUNTY, GEORGIA
<b>USE CALCULATIONS</b>	
TOTAL SITE AREA	25.132 ACRES
<b>MINIMUM SETBACKS</b>	
FRONT SETBACK	15 FEET
SIDE SETBACK	5 FEET
REAR SETBACK	20 FEET
EXTERIOR STREET BUILDING SETBACK	40 FEET (ADJACENT TO EXTERIOR STREETS)
EXTERIOR FRONT LANDSCAPE STRIP	10 FEET
<b>MINIMUM LOT REQUIREMENTS</b>	
MIN LOT WIDTH	60 FEET
MIN LOT AREA	7,200 SF (SEWER)
MIN HEATED FLOOR AREA PROVIDED	1,800 SF
MAX BUILDING HEIGHT	35 FEET
DETACHED SINGLE FAMILY LOTS PROVIDED	64 LOTS
TOTAL SITE DENSITY PROVIDED	2.76 LOTS
MAX NET SITE DENSITY ALLOWED	6.0 LPA
MAX LOT COVERAGE PER LOT	60% OF LOT
<b>MINIMUM PARKING REQUIREMENTS</b>	
MIN PARKING SPACES REQUIRED	132 SPACES @ 85' DWELLING UNIT
MAX PARKING SPACES REQUIRED	306 SPACES @ 85' DWELLING UNIT
PARKING PROVIDED	264 SPACES @ 2 DRIVE + 2 DRIVEWAY SP.
<b>OPEN SPACE</b>	
OPEN SPACE REQUIRED	10% (2,513 ACRES)
USABLE OPEN SPACE REQUIRED	9% (1,157 ACRES)
OPEN SPACE PROVIDED	3,349 ACRES @ 16.5% SITE
USABLE OPEN SPACE PROVIDED	1,547 ACRES @ 7.8% SITE



P: (770) 451-2741 F: (770) 451-3915  
 WWW.PECPLUS  
**PEC+**  
 Planners & Engineers Collaborative  
 LAND PLANNING • LANDSCAPE ARCHITECTURE • CIVIL ENGINEERING  
 ARCHITECTURE • SURVEYING & CONSTRUCTION • REAL ESTATE SERVICES  
 350 RESEARCH COURT STE 200  
 PEACHTREE CORNERS, GA 30092

PROJECT  
**RABBIT HILL CIR.**  
 A MASTER PLANNED RESIDENTIAL DEVELOPMENT

AT  
 2287 RABBIT HILL CIR.  
 DACULA, GEORGIA 30019  
 PARCEL ID (7018 002)

GWINNETT COUNTY JURISDICTION

FOR  
**INLINE COMMUNITIES**

RZR2024-00032

REVISIONS

NO.	DATE	BY	DESCRIPTION
1	05/17/2024	hax	Final Update to Zoning
2	05/17/2024	hax	Updated Zoning Plan

THIS SEAL IS ONLY VALID IF COUNTER SIGNED AND DATED WITH AN ORIGINAL SIGNATURE.

**GEORGIA**  
 STATE  
 3450  
 PROFESSIONAL  
 LAND SURVEYOR  
 12000  
 J. WOOD

GSWCC LEVEL II DESIGN PROFESSIONAL  
 CERTIFICATION # 000059388 EXP. 10/28/2024

**REZONING MASTER PLAN**

SCALE: 1" = 80'  
 DATE: 05/17/2024  
 PROJECT: 23038.01

**Z1**  
 SHEET

RZR2024-00032

Page 7 of 12


24 HOUR CONTACT:  
 BRIAN EHRSAM  
 WWW.GEORGIA811.COM  
**GWINNETT COUNTY**  
 PLANNING AND DEVELOPMENT

**RECEIVED**  
 5.17.24


**Exhibit C: Building Elevations**

**[attached]**






**ROOF PLAN "D"**  
 SCALE: 1/8"=1'-0" (11x17" SHEET SIZE)  
 SCALE: 1/8"=1'-0" (22x34" SHEET SIZE)



**BRACKET 18X18X4**  
 SCALE: 1/8"=1'-0" (11x17" SHEET SIZE)



**BRACKET 12X12X4**  
 SCALE: 1/8"=1'-0" (11x17" SHEET SIZE)



**FRONT ELEVATION "D"**  
 SCALE: 1/8"=1'-0" (11x17" SHEET SIZE)  
 SCALE: 1/4"=1'-0" (22x34" SHEET SIZE)

WINDOW PERCENTAGES	%
WINDOWS = 20.1	
15% REQUIRED TO MEET ZONING REQUIREMENT FOR FOURTH	

FACADE PERCENTAGES	
MATERIALS	S.F. %
SHINGLES	190 33
SHAKE	141 27
BOARD & BATT	0 0
HARDY BOARD	0 0
STONE VENEER	0 0
BRICK VENEER	345 60
TOTAL	576 100
MASONRY % = 60	

- 24'-0 3/4" MEAN BUILDING HEIGHT
- 9'-1" 2nd Level Plate Height
- 7'-8" Window Head Height
- 2nd Level Finished Floor
- 9'-1" 1st Level Plate Height
- 8'-0" Window Head Height
- 8" COLUMN W/ 18" SQ. BRICK BASE
- BRICK VENEER
- 1st Level Finished Floor
- 8'-6 1/2" Basement Plate Height
- 7'-8" Window Head Height
- Basement Finished Floor



**LEFT ELEVATION "D" W/ 9' BSMT.**  
 SCALE: 1/8"=1'-0" (11x17" SHEET SIZE)  
 SCALE: 1/8"=1'-0" (22x34" SHEET SIZE)


WINDOW PERCENTAGES	
WINDOWS = 5.5	
5% REQUIRED TO MEET ZONING REQUIREMENT FOR FOURTH	

GWINNETT COUNTY  
 PLANNING AND DEVELOPMENT

**RECEIVED**

RZR2024-00032

5.17.24



**OPT. EXT. OUTDOOR LIVING REAR ELEVATION**  
 SCALE: 1/8"=1'-0" (11x17" SHEET SIZE)  
 SCALE: 1/4"=1'-0" (22x34" SHEET SIZE)



**REAR ELEVATION "D" W/ 9' BSMT.**  
 SCALE: 1/8"=1'-0" (11x17" SHEET SIZE)  
 SCALE: 1/4"=1'-0" (22x34" SHEET SIZE)



**RIGHT ELEVATION "D" W/ 9' BSMT.**  
 SCALE: 1/8"=1'-0" (11x17" SHEET SIZE)  
 SCALE: 1/4"=1'-0" (22x34" SHEET SIZE)

RZR2024-00032

Page 16 of 62

**GWINNETT COUNTY  
 PLANNING AND DEVELOPMENT**

RECEIVED

5.17.24      BF

**MAIN STREET**  
 Design by  
 Main Street Design of Georgia, LLC  
 1000 Peachtree Street, Suite 200  
 Atlanta, GA 30309  
 Tel: 404.525.1000  
 www.mainstreetdesign.com


Revised Date:  
**11/03/2023**

Model: **Kirkwood**  
 Drawing Title: **Elevations Rear & Right w/ 9' Bsmt.**  
 Drawing File: \_\_\_\_\_  
 Option Description: \_\_\_\_\_


4400 North Point Parkway  
 Suite 295  
 Alpharetta, Georgia 30022  
 (770) 945-3600

**taylor morrison**  
 Homes Inspired by You

Plan Name: **Kirkwood**  
 Division: **Atlanta County**  
 Municipality: \_\_\_\_\_  
 Community: \_\_\_\_\_  
 Lot Number: \_\_\_\_\_  
 Scale: 1/8"=1'-0" / 22x34" - 1/4"=1'-0"  
 Unless Otherwise Noted  
 Sheet: **A-3.1D**



**ROOF PLAN "D"**  
 SCALE: 1/8"=1'-0" (11"x17" SHEET SIZE)  
 SCALE: 1/8"=1'-0" (22"x34" SHEET SIZE)



WINDOW PERCENTAGES	%
WINDOWS	6.4
1% REQUIRED TO MEET ZONING REQUIREMENT FOR FORESTH	

MATERIALS	S.F.	%
BRICK	150	13.3
SHAKE	100	9.0
BRICK BOND	5	0.4
STONE VENEER	164	14.8
BRICK VENEER	274	24.5
TOTAL	593	100
MASONRY		62

WINDOW PERCENTAGES	%
WINDOWS	6.4
1% REQUIRED TO MEET ZONING REQUIREMENT FOR FORESTH	



GWINNETT COUNTY  
 PLANNING AND DEVELOPMENT

**RECEIVED**

RZR2024-00032  
 5.17.24





**OPT. EXTENDED OUTDOOR LIVING  
PARTIAL REAR ELEVATION**  
SCALE: 1/8"=1'-0" (11"x17" SHEET SIZE)  
SCALE: 1/4"=1'-0" (22"x34" SHEET SIZE)



**REAR ELEVATION "D" W/ 9' BSMT.**  
SCALE: 1/8"=1'-0" (11"x17" SHEET SIZE)  
SCALE: 1/4"=1'-0" (22"x34" SHEET SIZE)



**RIGHT ELEVATION "D" W/ 9' BSMT.**  
SCALE: 1/8"=1'-0" (11"x17" SHEET SIZE)  
SCALE: 1/4"=1'-0" (22"x34" SHEET SIZE)

WINDOW PERCENTAGES	%
WINDOWS	6.7
5% REQUIREMENT	6.7
REQUIREMENT	6.7

RZR2024-00032

**GWINNETT COUNTY  
PLANNING AND DEVELOPMENT**

**RECEIVED**

5.17.24      BF

**Exhibit D: Letter of Intent and Applicant's Response to Standards**

**[attached]**



Matthew P. Benson  
Catherine W. Davidson  
Gerald Davidson, Jr.\*  
Brian T. Easley  
Rebecca B. Gober  
Christopher D. Holbrook  
Shane M. Lanham  
Jessica P. Kelly

Julia A. Maxwell  
Jeffrey R. Mahaffey  
Steven A. Pickens  
Jack M. Ryan  
Gabrielle H. Schaller  
S. Tess Shaheen  
Andrew D. Stancil  
R. Lee Tucker, Jr.

\*Of Counsel

**LETTER OF INTENT FOR REZONING APPLICATION**

Mahaffey Pickens Tucker, LLP submits this Letter of Intent and attached rezoning application (the “Application”) on behalf of Inline Communities, LLC (the “Applicant”) requesting the rezoning of an approximately 23.13-acre tract of land (the “Property”) situated along Rabbit Hill Circle east of its intersection with Old Peachtree Road. The Property is located within the Traditional/Traditional+ Future Development Area of the Gwinnett County 2045 Unified Plan (the “2045 Plan”) and is currently zoned RA-200.

The Applicant submits the Application requesting to rezone the Property to the R-60 (Single-Family Residence District) zoning classification of the Gwinnett County Unified Development Ordinance (the “UDO”) in order to develop the Property as an attractive single-family detached residential community with a total of 66 homes. Homes would be constructed with attractive architectural design and building materials as depicted in the renderings submitted with the Application and which would meet or exceed the requirements of the UDO’s Architectural Design Standards for Detached Residential Buildings. All of the homes would include two-car

GWINNETT COUNTY  
PLANNING AND DEVELOPMENT  
**RECEIVED**  
RZR2024-00032  
5.2.24

garages and would have a minimum heated floor area of 1,800 square feet. The proposed development would be accessed by a single entrance on Rabbit Hill Circle.

The proposed development is compatible with surrounding land uses and zoning classifications and fits within the established pattern of development. The surrounding area is characterized primarily by single-family detached residential development including communities zoned RZT, R-60, R-75, and R-100 CLU. To the south across Rabbit Hill Circle are two existing subdivisions with compatible zoning classifications and an undeveloped tract which was recently rezoned to the R-60 zoning classification. The Nichols Glen subdivision is zoned RZT with minimum 50-foot wide lots. The Apalachee Station subdivision is zoned both R-75 and R-100 CLU with lots that range from approximately 75 feet wide to 100 feet wide. Further south across Old Peachtree Road is the Preserve at Peachtree Shoals, a 55+, age-restricted, independent living retirement community. Commercial development within the city limits of Dacula is located to the south across Old Peachtree Road and Hurricane Shoals Road which includes a Circle K convenience store with fuel pumps, the Dacula Cork and Bottle package store, and a self-storage facility with RV parking. To the southeast across Hurricane Shoals is additional land zoned for commercial uses within the city limits of Dacula. To the north of the Property is the Ivey Chase subdivision zoned R-100 Modified. Even though the UDO does not require a buffer between R-60 and R-100 Modified, required stream buffers will provide appropriate screening and separation from that development in the form of 50-foot wide stream buffers which are required along a stream which meanders through the Property roughly parallel to its northern boundary line. Since the required stream buffer is 50 feet wide and is required on both sides of the stream, the provided buffer will be a minimum of 100 feet wide and, in most places, that 100-foot wide buffer will be provided entirely on the Property.

GWINNETT COUNTY  
PLANNING AND DEVELOPMENT

**RECEIVED**

RZR2024-00032

5.2.24

Generally, land uses and zoning classifications in the surrounding area are more intense at the core of the Hurricane Shoals/Old Peachtree Road node and transition downward in intensity moving away from the intersection. The proposed development fits squarely within that established transitional pattern by providing single-family detached lots that are a minimum of 60 feet wide pursuant to the R-60 zoning classification. The Property is also located in close proximity to right-of-way for the future Sugarloaf Parkway extension which crosses Hurricane Shoals Road just west of its intersection with Dacula Road. The Applicant submits that this large swath of right-of-way and the future extension of Sugarloaf Parkway provide additional supporting grounds for approval of the proposed development.

The proposed development is also in line with the policy and intent of the 2045 Plan which broadly promotes residential development and encourages a variety of housing types. Specifically, Chapter 4: Housing of the 2045 Plan provides abundant data and statistics that reflect a housing shortage in Gwinnett County. In the Needs & Opportunities section of Chapter 4, the 2045 Plan identifies a need of “More Housing Development” and provides that the “housing shortage inhibits population growth, business attraction, and other economic development by raising housing prices and failing to accommodate new residents.” The 2045 Plan crystalizes this policy when it provides that a “higher volume of housing development is needed to meet economic goals and countywide growth potential.”

The proposed development is also compatible with the 2045 Plan’s specific land use policies for the Property’s Future Development Area, which is “Traditional/Traditional+.” The main difference between the Traditional and Traditional+ Future Development Areas is the presence of sewer infrastructure. As set forth in the Sewer Capacity Certification submitted with

the Application, sewer is available to the Property and sufficient capacity exists in the system to

GWINNETT COUNTY  
PLANNING AND DEVELOPMENT  
**RECEIVED**  
RZR2024-00032  
5.2.24

serve the proposed development. Accordingly, the land use policies of the Traditional+ Future Development area are applicable to the Property. The 2045 Plan provides that R-60 is a recommended zoning classification for Traditional+. In fact, the 2045 Plan also lists the more intense zoning classifications of R-TH and TND as recommended. Traditional+ accommodates a variety of housing types including townhomes, quads/triplexes/duplexes, and single-family cottages—all of which would be provided on smaller lots and at higher densities than the single-family detached homes proposed by the Applicant.

In order to develop the Property as depicted on the site plan submitted with the application, the Applicant is requesting a variance to reduce the minimum required building setback for side yards of corner lots—specifically the side yard adjacent to the street. According to the UDO, corner lots are considered to have two front yards—one for each road frontage<sup>1</sup>. As a result, the UDO would require a setback of 15 feet in the front yard of the home as well as a setback of 15 feet in the side yard of the home which is adjacent to the right-of-way. The Applicant is proposing to reduce the required setback in the side yard of corner lots adjacent to the street to 10 feet as depicted on the typical lot layout on the site plan submitted with the Application. Accordingly, the Applicant requests a variance from UDO §210-120 to reduce the “second” front yard setback of corner lots from 15 feet to 10 feet. Additionally, the Applicant requests a waiver from UDO §360-90.1 to remove the requirement to install a sidewalk and curb ramp along the right-of-way of Rabbit Hill Circle to the east of the proposed development’s entrance. Rabbit Hill Circle abuts the Property along its southeasterly boundary and is a dead-end, substandard street, providing access to only a

---

<sup>1</sup> The UDO defines “Yard, Front” as an “open, unoccupied space on the same lot with a principal building or use, extending the full width of the lot and located between the street easement or right-of-way and the front line of the building projected parallel to the street projected to the side lines of the lot. Corner lots shall be considered to have two front yards.” UDO §110-40.

GWINNETT COUNTY  
PLANNING AND DEVELOPMENT

**RECEIVED**

RZR2024-00032

5.2.24

handful of homes. No portion of Rabbit Hill Circle east of Nichols Road contains a sidewalk and, according to Gwinnett County GIS maps, the Rabbit Hill Circle right-of-way terminates approximately 915 feet to the east of the Property. Accordingly, approval of the requested waiver would not impair the walkability of the surrounding area.

The Applicant and its representatives welcome the opportunity to meet with staff of the Gwinnett County Department of Planning & Development to answer any questions or to address any concerns relating to the matters set forth in this letter or in the Rezoning Application filed herewith. The Applicant respectfully requests your approval of these Applications.

Respectfully submitted this 2nd day of May, 2024.

MAHAFFEY PICKENS TUCKER, LLP

*Shane M. Lanham*

Shane M. Lanham  
*Attorneys for Applicant*

GWINNETT COUNTY  
PLANNING AND DEVELOPMENT

**RECEIVED**

RZR2024-00032

5.2.24



**REZONING APPLICANT'S RESPONSE**  
**STANDARDS GOVERNING THE EXERCISE OF THE ZONING POWER**

Pursuant to requirements of the Unified Development Ordinance, the Board of Commissioners find that the following standards are relevant in balancing the interest in promoting the public health, safety, morality, or general welfare against the right to the unrestricted use of the property and shall govern the exercise of the zoning power.

Please respond to the following standards in the space provided or use an attachment as necessary:

(A) Whether a proposed rezoning will permit a use that is suitable in view of the use and development of adjacent and nearby property:

---

---

(B) Whether a proposed rezoning will adversely affect the existing use or usability of adjacent or nearby property:

---

---

(C) Whether the property to be affected by a proposed rezoning has reasonable economic use as currently zoned:

---

---

(D) Whether the rezoning will result in a use which will or could cause an excessive or burdensome use of existing streets, transportation facilities, utilities, or schools:

---

---

(E) Whether the proposed rezoning is in conformity with the policy and intent of the Land Use Plan:

---

---

(F) Whether there are other existing or changing conditions affecting the use and development of the property which give supporting grounds for either approval or disapproval of the proposed rezoning:

---

---

**REZONING APPLICANT'S RESPONSE**  
**STANDARDS GOVERNING THE EXERCISE OF THE ZONING POWER**

- (A) Yes, approval of the proposed Rezoning Application will permit a use that is suitable in view of the use and development of adjacent and nearby property. The proposed residential development is compatible with existing residential uses and will further diversify housing options in the surrounding area.
- (B) No, approval of the proposed Rezoning Application will not adversely affect the existing use or usability of any of the nearby properties. Rather, the proposed development will complement the housing mix of the surrounding area.
- (C) Due to the size, location, layout and dimensions of the subject property, the Applicant submits that the property does not have reasonable economic use as currently zoned.
- (D) No, approval of the proposed rezoning will not result in an excessive or burdensome use of the infrastructure systems. The Property is located in close proximity to major transportation corridors including Old Peachtree Road, Hurricane Shoals Road, Dacula Road, and University Parkway (State Route 316). Water and sewer utilities are present in the area.
- (E) Yes, approval of the proposed rezoning is in conformity with the policy and intent of the Gwinnett County 2045 Unified Plan which encourages residential development. The subject property is located in the Traditional/Traditional+ Future Development Area. Based on the presence of sewer, the proposed development should be analyzed under the policies of the Traditional+ Future Development Area, which accommodates single-family detached housing and, specifically, the R-60 zoning classification.
- (F) The Applicant submits that the quality of the proposed homes, the character of surrounding development, and the future construction of the Sugarloaf Parkway extension provide additional supporting grounds for approval of the Application.

**JUSTIFICATION FOR REZONING**

The portions of the Gwinnett County Unified Development Ordinance (the “UDO”) which classify or may classify the property which is the subject of this Application (the “Property”) into any less intensive zoning classification other than as requested by the Applicant, are or would be unconstitutional in that they would destroy the Applicant's property rights without first paying fair, adequate and just compensation for such rights, in violation of Article I, Section I, Paragraph II of the Constitution of the State of Georgia of 1983, and the Due Process Clause of the Fourteenth Amendment to the Constitution of the United States.

The application of the UDO as applied to the subject Property, which restricts its use to the present zoning classification, is unconstitutional, illegal, null and void, constituting a taking of the Applicant's and the Owner’s property in violation of the Just Compensation Clause of the Fifth Amendment and the Due Process Clause of the Fourteenth Amendment to the Constitution of the United States, Article I, Section I, Paragraph I, and Article I, Section I, Paragraph II of the Constitution of the State of Georgia of 1983, and the Equal Protection Clause of the Fourteenth Amendment to the Constitution of the United States denying the Applicant an economically viable use of its land while not substantially advancing legitimate state interests.

The Property is presently suitable for development under the R-60 classification as requested by the Applicant, and is not economically suitable for development under the present RA-200 zoning classification of Gwinnett County. A denial of this Application would constitute an arbitrary and capricious act by the Gwinnett County Board of Commissioners without any rational basis therefore, constituting an abuse of discretion in violation of Article I, Section I, Paragraph I and Article I, Section I, Paragraph II of the Constitution of the State of Georgia of 1983, and the Due Process Clause of the Fourteenth Amendment to the Constitution of the United States.

A refusal by the Gwinnett County Board of Commissioners to rezone the Property to the R-60 classification with such conditions as agreed to by the Applicant, so as to permit the only feasible economic use of the Property, would be unconstitutional and discriminate in an arbitrary, capricious and unreasonable manner between the Applicant and owners of similarly situated

RECEIVED

5.2.24

property in violation of Article I, Section I, Paragraph II of the Constitution of the State of Georgia of 1983 and the Equal Protection Clause of the Fourteenth Amendment to the Constitution of the United States. Any rezoning of the subject Property to the R-60 classification, subject to conditions which are different from the conditions by which the Applicant may amend its application, to the extent such different conditions would have the effect of further restricting the Applicant's and the Owner's utilization of the subject Property, would also constitute an arbitrary, capricious and discriminatory act in zoning the Property to an unconstitutional classification and would likewise violate each of the provisions of the State and Federal Constitutions set forth hereinabove. Opponents to the request set forth in the Application, or in any amendments to the Application, have waived their rights to appeal any decision of the Gwinnett County Board of Commissioners because they lack standing, have failed to exhaust administrative remedies, and/or because they failed to assert any legal or constitutional objections.

Accordingly, the Applicant respectfully requests that the rezoning application submitted by the Applicant relative to the Property be granted and that the Property be rezoned to the zoning classification as shown on the respective application.

This 2nd day of May, 2024.

Respectfully submitted,

MAHAFFEY PICKENS TUCKER, LLP

*Shane M. Lanham*

Shane M. Lanham

*Attorneys for Applicant*

1550 North Brown Road  
Suite 125  
Lawrenceville, Georgia 30043  
(770) 232-0000

**Exhibit E: Application and Disclosure of Campaign Contributions**

**[attached]**



Please complete this application to amend the official zoning map of Gwinnett County and attach a letter of intent explaining what is proposed.

Applicant Information	Property Owner Information
Name: _____	Name: _____
Address: _____	Address: _____
City: _____	City: _____
State: _____ Zip code: _____	State: _____ Zip code: _____
Phone: _____	Phone: _____
Email: _____	Email: _____

Contact person: \_\_\_\_\_ Phone: \_\_\_\_\_

Contact's email: \_\_\_\_\_

**Applicant is the**

Owner's agent     
  Property owner     
  Contract purchaser

Present zoning district(s): \_\_\_\_\_ Requested zoning district: \_\_\_\_\_

Parcel number(s): \_\_\_\_\_ Acreage: \_\_\_\_\_

Address of property: \_\_\_\_\_


Proposed development: \_\_\_\_\_

RESIDENTIAL DEVELOPMENT	NON-RESIDENTIAL DEVELOPMENT
No. of Lots/Dwelling Units _____	No. of Buildings/Lots: _____
Dwelling Unit Size (Sq. Ft.): _____	Total Building Sq. Ft. _____
Gross Density: _____	Density: _____
Net Density: _____	



**REZONING APPLICANT'S CERTIFICATION**

The undersigned below is authorized to make this application. The undersigned is aware that no application or reapplication affecting the same land shall be acted upon within 12 months from the date of last action by the Board of Commissioners unless waived by the Board of Commissioners. In no case shall an application or reapplication be acted upon in less than six months from the date of last action by the Board of Commissioners.



Signature of applicant

3/27/24

Date

Shane Lanham, attorney for Applicant


Type or print name and title



Signature of notary public

3/27/24

Date



Notary seal

GWINNETT COUNTY  
PLANNING AND DEVELOPMENT

**RECEIVED**

5. RZ 2024-00032

REZONING APPLICATION 3 | 7

**REZONING APPLICANT'S CERTIFICATION**

The undersigned below is authorized to make this application. The undersigned is aware that no application or reapplication affecting the same land shall be acted upon within six (6) months from the date of last action by the Board of Commissioners.

  
Signature of Applicant

5/1/2024  
Date

InLine Communities, LLC - Brian Ehram, Project Manager  
Type or Print Name and Title

  
Signature of Notary Public

5/1/2024  
Date



GWINNETT COUNTY  
PLANNING AND DEVELOPMENT  
**RECEIVED**  
RZR2024-00032  
5.2.24



**REZONING PROPERTY OWNER'S CERTIFICATION**

THE UNDERSIGNED BELOW, OR AS ATTACHED, IS THE OWNER OF THE PROPERTY CONSIDERED IN THIS APPLICATION. THE UNDERSIGNED IS AWARE THAT NO APPLICATION OR REAPPLICATION AFFECTING THE SAME LAND SHALL BE ACTED UPON WITHIN 12 MONTHS FROM THE DATE OF LAST ACTION BY THE BOARD OF COMMISSIONERS UNLESS WAIVED BY THE BOARD OF COMMISSIONERS. IN NO CASE SHALL AN APPLICATION OR REAPPLICATION BE ACTED UPON IN LESS THAN SIX (6) MONTHS FROM THE DATE OF LAST ACTION BY THE BOARD OF COMMISSIONERS.

Carlton R Dills 03-11-2024  
Signature of Property Owner Date

Carlton R. Dills, Owner CARLTON R DILLS CO OWNER  
Type or Print Name and Title

Susan Utt 3/11/2024  
Signature of Notary Public Date



**REZONING PROPERTY OWNER'S CERTIFICATION**

THE UNDERSIGNED BELOW, OR AS ATTACHED, IS THE OWNER OF THE PROPERTY CONSIDERED IN THIS APPLICATION. THE UNDERSIGNED IS AWARE THAT NO APPLICATION OR REAPPLICATION AFFECTING THE SAME LAND SHALL BE ACTED UPON WITHIN 12 MONTHS FROM THE DATE OF LAST ACTION BY THE BOARD OF COMMISSIONERS UNLESS WAIVED BY THE BOARD OF COMMISSIONERS. IN NO CASE SHALL AN APPLICATION OR REAPPLICATION BE ACTED UPON IN LESS THAN SIX (6) MONTHS FROM THE DATE OF LAST ACTION BY THE BOARD OF COMMISSIONERS.

Clyde Nichols 3/8/24  
Signature of Property Owner Date

Clyde Nichols, Owner Clyde Nichols Co owner  
Type or Print Name and Title


Susan Utt 3/8/2024  
Signature of Notary Public Date




GWINNETT COUNTY  
PLANNING AND DEVELOPMENT  
**RECEIVED**  
RZR2024-00032  
5.2.24


**CONFLICT OF INTEREST CERTIFICATION FOR REZONING**

The undersigned below, applying for a rezoning, has complied with the Official Code of Georgia Section 36-67A-1 and has submitted or attached the required information on the forms provided.

 \_\_\_\_\_ 3/27/24  
*Signature of applicant* *Date*

Shane Lanham, attorney for Applicant  
 \_\_\_\_\_  
*Type or print name and title*

 \_\_\_\_\_ 3/27/24  
*Signature of notary public* *Date*



**DISCLOSURE OF CAMPAIGN CONTRIBUTIONS**

Have you, within the two years immediately preceding the filing of this application, made campaign contributions aggregating \$250 or more to a member of the Gwinnett County Board of Commissioners or a member of the Gwinnett County Planning Commission?

Yes       No Mahaffey Pickens Tucker, LLP  
*Name*

If the answer is yes, please complete the following section:

Name and Official Position of Government Official	Contributions (List all which aggregate to \$250 or more)	Date Contribution Was Made (Within last two years)
Please see attached		

**Attach additional sheets if necessary to disclose or describe all contributions.**



**CONFLICT OF INTEREST CERTIFICATION FOR REZONING/CHANGE IN  
CONDITIONS AND SPECIAL USE PERMIT APPLICATIONS**

**MAHAFFEY PICKENS TUCKER, LLP**

NAME AND OFFICIAL POSITION OF GOVERNMENT OFFICIAL	CONTRIBUTIONS	DATE
Ben Ku, Commissioner	\$1,500	10/03/2022
Matt Holtkamp, Commissioner	\$1,000	04/13/2023
Nicole Love Hendrickson, Chairwoman	\$2,500	08/11/2023
Matt Holtkamp, Commissioner	\$3,300	09/18/2023
Kirkland Carden, Commissioner	\$3,300	09/27/2023

**Lee Tucker, Attorney at Law, P.C.**

NAME AND OFFICIAL POSITION OF GOVERNMENT OFFICIAL	CONTRIBUTIONS	DATE
Kirkland Carden, Commissioner	\$2,000	10/25/2023

**Jeffrey Mahaffey, Attorney at Law, Individually**

NAME AND OFFICIAL POSITION OF GOVERNMENT OFFICIAL	CONTRIBUTIONS	DATE
Nicole Love Hendrickson, Chairwoman	\$1,000	08/14/2023

GWINNETT COUNTY  
PLANNING AND DEVELOPMENT


**RECEIVED**

RZR2024-00032  
5.2.24




**CONFLICT OF INTEREST CERTIFICATION FOR REZONING**

The undersigned below, making application for a rezoning, has complied with the Official Code of Georgia Section 36-67A-1, et. seq, Conflict of Interest in Zoning Actions, and has submitted or attached the required information on the forms provided.

 5/1/2024 Brian Ehrsam, Project Manager  
 Signature of Applicant Date Type of Print Name and Title

\_\_\_\_\_  
 Signature of Applicant's Attorney or Representative Date Type or Print Name and Title

 5/1/2024  
 Signature of Notary Public Date



**DISCLOSURE OF CAMPAIGN CONTRIBUTIONS**

Have you, within the two years immediately preceding the filing of this application, made campaign contributions aggregating \$250.00 or more to a member of the Board of Commissioners?

Yes  No Brian Ehrsam (Your Name)

If the answer is yes, please complete the following section:

NAME AND OFFICIAL POSITION OF GOVERNMENT OFFICIAL	CONTRIBUTIONS (List all which aggregate to \$250 or More)	DATE CONTRIBUTION WAS MADE (Within last two years)

Attach additional sheets if necessary to disclose or describe all contributions.




VERIFICATION OF CURRENT PAID PROPERTY TAXES FOR REZONING

The undersigned below is authorized to make this application. The undersigned certifies that all Gwinnett County property taxes billed to date for the parcel listed below have been paid in full to the Gwinnett County Tax Commissioner. In no case shall an application or reapplication for rezoning be processed without such property verification.

Note: A separate verification form must be completed for each tax parcel included in the rezoning request.

Parcel ID Number: 7 018 002  
 (Map reference number) *District Land lot Parcel*

 3/27/24  
*Signature of applicant Date*

Shane Lanham, attorney for Applicant 3/27/24  
*Type or print name and title Date*

\*\*\*Please take this form to the Tax Commissioners office at the Gwinnett Justice and Administration Center, located at 75 Langley Drive in Lawrenceville, for their approval below.\*\*\*

TAX COMMISSIONERS USE ONLY

Payment of all property taxes billed to date for the above referenced parcel has been verified as paid current and confirmed by the signature below.

Jessilyn McDuffie TSA  
*Name Title*

3/27/24  
*Date*



**Exhibit F: DWR Sewer Capacity Certification Letter**

**[attached]**



April 4, 2024

Brian Eshram  
Inline Communities  
1776 Peachtree St NW #2065  
Atlanta, GA 30309

<input checked="" type="checkbox"/>	<b>APPROVED</b>
<input type="checkbox"/>	<b>DENIED</b>
<input type="checkbox"/>	<b>CONDITIONALLY APPROVED</b>
<b>Sewer Capacity Request #C2024-070-04</b>	
<b>Expiration Date: 04/04/2025</b>	
<b>Tie-In Manhole FID: 205442</b>	

RE: Sewer Availability for Proposed Development – 2287 Rabbit Hill Circle - North Parcel  
Parcel ID 7018 002

Dear Mr. Eshram:

This letter supersedes the earlier Sewer Capacity Certification C2023-090-05 dated December 15, 2023 addressed to Matt Stokes of Chafin Communities.

Gwinnett County Department of Water Resources (GCDWR) has reviewed the impact of the proposed development consisting of 66 single-family homes on the above parcel and determined:

Gwinnett County has adequate sewer capacity to serve the proposed development.

This confirmation is based on your anticipated annual average daily flow of 11.46 gpm discharging to the sewer tie-in manhole at Facility ID **205442**.

**Capacity Allocation:** Sewer capacities are allocated only upon the issuance of a Development Permit, by Gwinnett County Planning & Development and after all applicable conditions established in this Sewer Capacity Certification, if any, are met.

**Certification Expiration:** The Sewer Capacity Certification is valid for 12 months from the date of this letter. If rezoning is approved, GCDWR will issue a revised Sewer Capacity Certification based on the approved units, as needed. The capacity request can be renewed for an additional 12 months. If a Development Permit has not been obtained by the expiration date above the developer may apply for renewal by providing evidence of active rezoning, plan review, or permitting efforts.

Once the Sewer Capacity Certification expires, the capacity is no longer allocated, and a new Sewer Capacity Certification request must be submitted for re-evaluation with no guarantee of available capacity. The evaluation will be based on the updated conditions of the sewer system.

**Certification Invalidation:** This certification is not valid if there are proposed changes to your development that could impact downstream sewer capacity (e.g. land use density, sewer tie-in





manhole, parcel changes, and/or rezoning). In this case the development must resubmit for a new Sewer Capacity Request with updated information prior to the expiration of the previous one.

Please contact us at 678-376-7026 if you have any questions.

Sincerely,

GWINNETT COUNTY DEPARTMENT OF WATER RESOURCES

Tai Yi Su, PE  
Division Director, Infrastructure Support  
678.376.2104

C: Gwinnett County DWR – Lorraine Campagne, Section Manager; Raghu Vemuru, Engineer V; Mikala Weston, Engineer III  
Gwinnett County P&D – Charli Young, Planning Manager; Geniva Sylvain, Engineer I; Christina Dejarnette, Engineer I

**Exhibit G: Traffic Impact Study**

**[attached]**

**RECEIVED**

5.2.24

**TRAFFIC IMPACT STUDY  
FOR  
RESIDENTIAL DEVELOPMENT  
AT RABBIT HILL CIRCLE AND TURKEY ROAD  
GWINNETT COUNTY, GEORGIA**



***Prepared for:***

***InLine Communities, LLC  
1776 Peachtree Street NW – Suite 260S  
Atlanta, GA 30309***

***Prepared By:***



**A&R Engineering Inc.**

2160 Kingston Court, Suite O  
Marietta, GA 30067  
Tel: (770) 690-9255 Fax: (770) 690-9210  
[www.areng.com](http://www.areng.com)

April 19, 2024  
A & R Project # 24-060

**RECEIVED**

5.2.24

## 5.2 Existing Traffic Operations

Existing 2024 traffic operations were analyzed at the study intersections in accordance with the HCM methodology. The results of the analyses are shown in Table 3.

TABLE 3 – EXISTING INTERSECTION OPERATIONS				
Intersection		Traffic Control	LOS (Delay)	
			AM Peak Hour	PM Peak Hour
1	<b><u>Rabbit Hill Circle / Nichols Road @ Turkey Road</u></b>	Stop Controlled on SB Approach	A (7.3)	A (7.2)
	-Eastbound Left -Southbound Approach		A (8.4)	A (8.7)
2	<b><u>Rabbit Hill Circle @ Old Peachtree Road</u></b>	Stop Controlled on WB Approach	C (15.2)	C (19.1)
	-Westbound Approach -Southbound Left		A (8.1)	A (8.2)
3	<b><u>Old Peachtree Road @ Hurricane Shoals Road</u></b>	Signalized	<b><u>B (19.2)</u></b>	<b><u>C (25.2)</u></b>
	-Eastbound Approach		C (33.4)	D (38.4)
	-Westbound Approach		D (35.5)	C (29.4)
	-Northbound Approach		A (9.5)	B (13.5)
	-Southbound Approach		B (10.9)	B (15.4)

The results of the existing traffic operations analysis indicate that the signalized intersection of Old Peachtree Road at Hurricane Shoals Road is operating at an overall level of service “C” or better in both the AM and PM peak hours, while the stop-controlled approaches at the unsignalized study intersections are operating at a level of service “C” or better with peak hour traffic.

**RECEIVED**

5.2.24

## 6.0 PROPOSED DEVELOPMENT

The proposed residential development will be located at 2287 Rabbit Hill Circle in Gwinnett County, Georgia. The development will consist of 66 single-family detached houses and proposes one full access driveway on Turkey Road.



A site plan is shown in Figure 5.



**RECEIVED**

5.2.24

## 6.1 Trip Generation

Trip generation estimates for the project were based on the rates and equations published in the 11<sup>th</sup> edition of the Institute of Transportation Engineers (ITE) Trip Generation report. This reference contains traffic volume count data collected at similar facilities nationwide. The trip generation was based on the ITE land use category 215 - *Single-Family Attached Housing*. The calculated total trip generation for the proposed development is shown in Table 4.

TABLE 4— TRIP GENERATION (PROPOSED SITE)								
Land Use	Size	AM Peak Hour			PM Peak Hour			24 Hour
		Enter	Exit	Total	Enter	Exit	Total	Two-Way
<b>ITE 210 – Single-Family Detached Housing</b>	66 Units	13	38	51	42	25	67	688

## 6.2 Trip Distribution

The trip distribution describes how traffic arrives and departs from the site. An overall trip distribution was developed for the site based on a review of the existing travel patterns in the area and the locations of major roadways and highways that will serve the development. The site-generated peak hour traffic volumes, shown in Table 4, were assigned to the study area intersections based on this distribution. The outer-leg distribution and AM and PM peak hour new traffic generated by the site are shown in Figure 6.

### 6.2.1 Adjacent Residential Development – Traffic Impact Study 23-062

There is a planned 67-house residential development to the south of the proposed site and Turkey Road (A traffic impact study was completed for it in June 2023). Because this project is estimated to be completed before 2028, its impact on the study area was considered in both the “No Build” and “Build” conditions analyses. The ITE site-generated traffic volumes for this development are shown in Table 5, and the AM and PM peak hour volumes passing through the study area are shown in Figure 7.

TABLE 5— TRIP GENERATION (ADJACENT SITE)								
Land Use	Size	AM Peak Hour			PM Peak Hour			24 Hour
		Enter	Exit	Total	Enter	Exit	Total	Two-Way
<b>ITE 210 – Single-Family Detached Housing</b>	67 Units	13	39	52	43	25	68	698

**RECEIVED**

5.2.24

## 7.4 Future Traffic Operations

The future “No-Build” and “Build” traffic operations were analyzed using the volumes in Figures 8 and 9, respectively. The results of the future traffic operations analysis are shown below in Table 6. Recommendations on traffic control and lane geometry are shown in Figure 10.

TABLE 6 – FUTURE INTERSECTION OPERATIONS					
Intersection		Future Condition: LOS (Delay)			
		NO-BUILD		BUILD-OUT	
		AM Peak	PM Peak	AM Peak	PM Peak
<b>1</b>	<b><u>Rabbit Hill Circle / Nichols Road @ Turkey Road</u></b>				
	-Eastbound Left	A (7.3)	A (7.3)	A (7.3)	A (7.3)
	-Southbound Approach	A (8.5)	A (9.0)	A (8.7)	A (8.5)
<b>2</b>	<b><u>Rabbit Hill Circle @ Old Peachtree Road</u></b>				
	-Westbound Approach	C (15.6)	C (18.2)	C (18.2)	C (21.3)
	-Southbound Left	A (8.2)	A (8.4)	A (8.3)	A (8.5)
<b>3</b>	<b><u>Old Peachtree Road @ Hurricane Shoals Road</u></b>	<b>B (19.7)</b>	<b>C (25.3)</b>	<b>B (19.7)</b>	<b>C (25.4)</b>
	-Eastbound Approach	C (32.5)	D (36.9)	C (32.5)	D (37.0)
	-Westbound Approach	D (34.6)	C (28.7)	D (34.3)	C (28.7)
	-Northbound Approach	B (10.6)	B (15.0)	B (10.8)	B (15.2)
	-Southbound Approach	B (12.0)	B (17.0)	B (12.2)	B (17.1)
<b>4</b>	<b><u>Turkey Road @ Site Driveway</u></b>				
	-Eastbound Approach	-	-	A (8.5)	A (8.4)
	-Northbound Left			A (7.2)	A (7.3)

The results of the future “No-Build” and “Build” conditions traffic analyses indicate that the signalized study intersection of Old Peachtree Road and Hurricane Shoals Road will be operating at an overall level of service “C” or better in both the AM and PM peak hours, while the stop-controlled approaches the unsignalized study intersections will continue to operate at a level of service “C” or better with peak hour traffic.

RECEIVED

5.2.24

## 8.0 CONCLUSIONS AND RECOMMENDATIONS

Traffic impacts were evaluated for the proposed residential development that will be located at 2287 Rabbit Hill Circle in Gwinnett County, Georgia. The development will consist of 66 single-family detached houses and proposes one full access driveway on Turkey Road.

Existing and future operations after completion of the project were analyzed at the intersections of:

- Rabbit Hill Circle / Nichols Road at Turkey Road
- Old Peachtree Road at Rabbit Hill Circle
- Hurricane Shoals Road at Old Peachtree Road
- Turkey Road at Site Driveway

The analysis included the evaluation of future operations for “No-Build” and “Build” conditions, with the differences between “No-Build” and “Build” accounting for the increase in traffic due to the proposed development. The results of the future “No-Build” and “Build” conditions traffic analyses indicate that the signalized study intersection of Old Peachtree Road and Hurricane Shoals Road will be operating at an overall level of service “C” or better in both the AM and PM peak hours, while the stop-controlled approaches the unsignalized study intersections will continue to operate at a level of service “C” or better with peak hour traffic. Based on the analysis, the proposed development will have minimal impact on traffic operations in the study network.

### 8.1 Recommendations for Site Access Configuration

The following access configuration is recommended for the proposed site driveway intersection:

- Site Driveway: Full Access Driveway on Turkey Road
  - One entering lane and one exiting lane
  - Stop-sign controlled on the driveway approach with Turkey Road remaining free flow
  - Widen/repave the length of Turkey Road from Rabbit Hill Road intersection up to the site driveway to comply with Gwinnett County standards (Turkey Road is a narrow 12-ft wide roadway, and it will need to be widened to accommodate any considerable increases in traffic)

**Exhibit H: Public Participation Plan and Report**

**[attached]**

---

## Public Participation Plan

- 1. Who do you intend to contact in addition to property owners within 1,000 feet of the site, if any?**

The Applicant will send mailers to owners of property within 1,000 feet of the subject property. The Applicant will also reach out via phone and/or email to contacts it established during a previous rezoning in the area.

---

- 2. Where do you plan to host the Public Participation Meeting? Ensure that the meeting is held in person at a convenient location for interested parties.**

The PPM will be held at Rabbit Hill Park, which is located less than one mile from the subject property.

---

---

- 3. What date and time do you plan to host the Public Participation Meeting? Ensure that the meeting is held at a convenient time for interested parties, e.g. not during typical work hours on weekdays.**

The PPM will be held on May 30 at 6:00 pm.

---

---

- 4. What is your method for providing opportunities for discussion with interested parties at the Public Participation Meeting?**

The Applicant will present an overview of the proposed development as well as an outline of Gwinnett County's rezoning process. After its presentation, the Applicant will open the floor for discussion with attendees

---

---

---

---



---

## Public Participation Report

1. List all groups that you notified of the requested application. Include a copy of the notification package and stamped Postal Service Form 3877 (attached) with itemized name and address of each addressee.

---

---

2. Provide the date, time, and location of all meeting(s) that the applicant and/or representative attended to discuss an application with interested parties.

---

---

3. Provide the number of people who participated in the meeting(s). Include the sign-in sheet(s) with meeting date, time, location, and attendee names.

---

---

4. What issues and concerns were expressed by attendees at the meeting(s)?

---

---

---

---

5. What are the applicant's responses to the issues and concerns that were expressed at the meetings? What changes to the development will be made?

---

---

---

---

**AMENDMENT TO AN APPLICATION TO AMEND THE OFFICIAL  
ZONING MAP OF GWINNETT COUNTY, GEORGIA**

APPLICANT: Inline Communities, LLC. c/o Mahaffey  
Pickens Tucker, LLP

ZONING CASE NUMBER: RZR2024-00032

PRESENT ZONING DISTRICT(S): RA-200

REQUESTED ZONING DISTRICT(S): R-60

PROPERTY: 2287 Rabbit Hill Circle

SIZE: +/- 23.13

PROPOSED DEVELOPMENT: Single-family detached residential community

The Applicant, Inline Communities, LLC, hereby amends its application to amend the official zoning map of Gwinnett County, Georgia heretofore filed with the Planning Division of Gwinnett County, Georgia by the addition of the attached Exhibit to the original application.

This 6th day of June, 2024.

MAHAFFEY PICKENS TUCKER, LLP

*Shane M. Lanham*

Shane M. Lanham  
*Attorneys for Applicant*

GWINNETT COUNTY  
PLANNING AND DEVELOPMENT

**RECEIVED**

RZR2024-00032  
6.6.24



Matthew P. Benson  
Catherine W. Davidson  
Gerald Davidson, Jr.\*  
Brian T. Easley  
Rebecca B. Gober  
Christopher D. Holbrook  
Shane M. Lanham  
Jessica P. Kelly

Julia A. Maxwell  
Jeffrey R. Mahaffey  
Steven A. Pickens  
Jack M. Ryan  
Gabrielle H. Schaller  
S. Tess Shaheen  
Andrew D. Stancil  
R. Lee Tucker, Jr.

Author's Email:  
slanham@mptlawfirm.com

\*Of Counsel

**VIA EMAIL**

Gwinnett County Planning and Development Department  
[P&D-PlanningZoning@gwinnettcountry.com](mailto:P&D-PlanningZoning@gwinnettcountry.com)  
Attn: Brian Ford  
[Brian.Ford@gwinnettcountry.com](mailto:Brian.Ford@gwinnettcountry.com)

Brian,

The Applicant held its public participation meeting on May 30. There was an encouraging amount of neighbor interest in the proposed development. The Applicant was able to have productive dialogue with the neighbors about their concerns and how the Applicant could work to tie in improvements to the development that will positively impact the entire community.

In response to the neighbors' concerns about rentals, the Applicant hereby incorporates a rental restriction of 5% into its rezoning application to reassure the neighbors that the homes will be owner occupied. The proposed development will also have a mandatory HOA, and the HOA documents will prohibit more than 5% of the homes being rented.

Please confirm receipt of this letter and its incorporation into the Applicant's application package. Please contact me if you wish to discuss further.

Sincerely,

MAHAFFEY PICKENS TUCKER, LLP

*Shane M. Lanham*

Shane M. Lanham  
*Attorneys for Applicant*

Sugarloaf Office || 1550 North Brown Road, Suite 125, Lawrenceville, Georgia 30043  
NorthPoint Office || 11175 Cicero Drive, Suite 100, Alpharetta, Georgia 30022  
TELEPHONE 770 232 0000  
FACSIMILE 678 518 6880  
www.mptlawfirm.com

GWINNETT COUNTY  
PLANNING AND DEVELOPMENT  
**RECEIVED**  
RZR2024-00032  
6.6.24

**Exhibit I: Internal and External Agency Review Comments**

**[attached]**



**Department of Planning and Development  
TECHNICAL REVIEW COMMITTEE**

<b>TRC Meeting Date:</b>		06.05.2024	
Department/Agency Name:		Transportation	
Reviewer Name:		Brent Hodges	
Reviewer Title:		Construction Manager 2	
Reviewer Email Address:		<a href="mailto:Brent.Hodges@gwinnettcountry.com">Brent.Hodges@gwinnettcountry.com</a>	
Case Number:		RZR2024-00032	
Case Address:		2287 Rabbit Hill Circle, Dacula, 30019	
<b>Comments:</b>		<input checked="" type="checkbox"/>	<input type="checkbox"/>
		<b>YES</b>	<b>NO</b>
1	Rabbit Hill Circle is a local street. No ADT on file.		
2	6.3 miles to the nearest Ride Gwinnett facility located at Collins Hill Road and Collins Industrial Way.		
3	Per section 360-90 of the UDO, the developer shall construct a 5' concrete sidewalk along the entire site frontage.		
4	Traffic Calming shall be provided for any internal street that exceeds 500' without a control point.		
5	Based on the traffic impact study submitted by the applicant; the results of the future 'build' and 'no-build' conditions indicate that the signalized intersection of Old Peachtree Road and Hurricane Shoals Road will continue to operate at a level of service (LOS) C in both the AM and PM peak hours.		
6	The submitted TIS also indicates that the stop-controlled intersections of Old Peachtree Road and Rabbit Hill Circle will continue to operate at a minimum LOS of C in the AM and PM peak hours.		
7			
<b>Recommended Zoning Conditions:</b>		<input checked="" type="checkbox"/>	<input type="checkbox"/>
		<b>YES</b>	<b>NO</b>
1	For the intersection of Rabbit Hill Circle / Nichols Road and Turkey Road; the developer shall make this either be a 3-way stop controlled intersection or realign as a "T" intersection.		
2	The developer shall upgrade Turkey Road to minimum standards for a Gwinnett County Department of Transportation local road, for the entire frontage of the site.		
3			
4			
5			
6			

**Note:** Attach additional pages, if needed

Revised 7/26/2021






**Department of Planning and Development  
TECHNICAL REVIEW COMMITTEE**

<b>TRC Meeting Date:</b>				
Department/Agency Name:		DWR		
Reviewer Name:		Mike Pappas		
Reviewer Title:		GIS Planning Manager		
Reviewer Email Address:		<a href="mailto:Michael.pappas@gwinnettcounty.com">Michael.pappas@gwinnettcounty.com</a>		
Case Number:		RZR2024-00032		
Case Address:		2287 Rabbit Hill Circle		
<b>Comments:</b>		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1	Water: The proposed development shall coordinate with GCDWR on connections to the existing water main on Rabbit Hill Circle. Upsizing of 2,400 linear feet of the existing 2-inch water main on Rabbit Hill Circle may be required.			
2	Sewer: A Sewer Capacity Certification (C2024-070-04) has been approved for 66 residential units. The proposed development plans to connect to an existing 8-inch gravity sewer located on parcel 2001 292. Easements will be required.			
3				
4				
5				
6				
7				
<b>Recommended Zoning Conditions:</b>		<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
1				
2				
3				
4				
5				
6				
7				

**Note:** Attach additional pages, if needed

*Revised 7/26/2021*



**LEGEND**


- Water Main
- Master Vault
- Regional
- Manhole
- Sewer Collector
- Sewer Interceptor
- Sewer Force Main

**2287 Rabbit Hill Cir**  
RA-200 to R-60

## Water & Sewer Utility Map

**LOCATION**

0 510 1,020  
Feet



**Water Comments:** The proposed development shall coordinate with GCDWR on connections to the existing water main on Rabbit Hill Circle. Upsizing of 2,400 linear feet of the existing 2-inch water main on Rabbit Hill Circle may be required.

**Sewer Comments:** A Sewer Capacity Certification (C2024-070-04) has been approved for 66 residential units. The proposed development plans to connect to an existing 8-inch gravity sewer located on parcel 2001 292. Easements will be required.

**Water Availability:** Water demands imposed by the proposed development may require upsizing or extensions of existing water mains in order to meet Gwinnett County Standards and fire flow demands. Any cost associated with such required improvements will be the responsibility of the development. Current Gwinnett County Standards require a minimum of 12" pipe size for commercial developments and a minimum of 8" pipe size for residential developments. Additionally, connection to a minimum of 12" and 8" mains are required for commercial and residential developments, respectively. It is the responsibility of the developer's engineer to confirm pressure and volumes are available for the development.

**Sewer Availability:** A Sewer Capacity Certification must be obtained from Gwinnett County to confirm the existing system can serve the development. Sewer demands imposed by the proposed development may require upsizing and/or extensions of existing sewer mains, and/or upsizing of an existing pump station, and/or installation of a new pump station. Any cost associated with such required improvements will be the responsibility of the development. The developer shall provide easements for future sewer connection to all locations designated by Gwinnett County during plan review.

**Water and Sewer Design and Construction Requirements:** Extensions of the water and/or sanitary sewer systems within the subject development must conform to this department's policies, Gwinnett County's ordinances, and the Water Main and Sanitary Sewer Design and Construction Standards and Specifications, dated April 5th, 2016. Subsequent to design, construction, inspection, and final acceptance of the required utilities, service would then become available under the applicable utility permit rate schedules.

**Private Road Developments:** Any development with private roads must comply with the Standard Policy Requirement for the Installation of Water and Sanitary Sewer Mains within Private Developments. This policy stipulates minimum easement requirements and location of public mains and appurtenances, among other requirements.

**Residential Rezoning Impact on Local Schools**  
**Prepared for Gwinnett County BOC, July, 2024**

											Proposed Zoning	
	School	2024-25			2025-26			2026-27			Approximate Student Projections from Proposed Developments	
		Forecast	Capacity	+/- Cap.	Forecast	Capacity	+/- Cap.	Forecast	Capacity	+/- Cap.		
RZM2024-00007	<b>Archer High School</b>	<b>2,950</b>	2,850	100	<b>2,887</b>	2,850	37	<b>2,863</b>	2,850	13	11	
	McConnell Middle School	<b>2,096</b>	1,775	321	<b>2,121</b>	1,775	346	<b>2,185</b>	1,775	410	8	
	Cooper Elementary School	<b>1,511</b>	1,625	-114	<b>1,527</b>	1,625	-98	<b>1,543</b>	1,625	-82	15	
RZM2024-00008	<b>Grayson High School</b>	<b>3,585</b>	3,000	585	<b>3,693</b>	3,000	693	<b>3,803</b>	3,000	803	25	
	Bay Creek Middle School	<b>1,449</b>	1,150	299	<b>1,485</b>	1,150	335	<b>1,537</b>	1,150	387	19	
	Trip Elementary School	<b>1,440</b>	1,200	240	<b>1,498</b>	1,200	298	<b>1,558</b>	1,200	358	36	
RZR2024-00023	<b>Dacula High School</b>	<b>2,553</b>	2,550	3	<b>2,617</b>	2,550	67	<b>2,682</b>	2,550	132	16	
	Dacula Middle School	<b>1,855</b>	1,900	-45	<b>1,901</b>	1,900	1	<b>1,949</b>	1,900	49	11	
	Mulberry Elementary School	<b>790</b>	975	-185	<b>826</b>	975	-149	<b>871</b>	975	-104	21	
RZR2024-00030	<b>Dacula High School</b>	<b>2,553</b>	2,550	3	<b>2,617</b>	2,550	67	<b>2,682</b>	2,550	132	3	
	Dacula Middle School	<b>1,855</b>	1,900	-45	<b>1,901</b>	1,900	1	<b>1,949</b>	1,900	49	1	
	Alcova Elementary School	<b>1,501</b>	1,150	351	<b>1,554</b>	1,150	404	<b>1,608</b>	1,150	458	3	
RZR2024-00032	<b>Mountain View High School</b>	<b>2,226</b>	2,300	-74	<b>2,209</b>	2,300	-91	<b>2,253</b>	2,300	-47	21	
	Twin Rivers Middle School	<b>1,683</b>	2,150	-467	<b>1,700</b>	2,150	-450	<b>1,734</b>	2,150	-416	15	
	Dyer Elementary School	<b>929</b>	1,175	-246	<b>903</b>	1,175	-272	<b>894</b>	1,175	-281	30	
RZR2024-00033	<b>Grayson High School</b>	<b>3,585</b>	3,000	585	<b>3,693</b>	3,000	693	<b>3,803</b>	3,000	803	57	
	Couch Middle School	<b>1,139</b>	1,150	-11	<b>1,167</b>	1,150	17	<b>1,197</b>	1,150	47	45	
	Starling Elementary School	<b>1,322</b>	1,200	122	<b>1,348</b>	1,200	148	<b>1,375</b>	1,200	175	80	
RZR2024-00034	<b>Seckinger High School</b>	<b>2,326</b>	2,800	-474	<b>2,452</b>	2,800	-348	<b>2,550</b>	2,800	-250	1	
	Jones Middle School	<b>1,820</b>	1,575	245	<b>1,893</b>	1,575	318	<b>1,969</b>	1,575	394	1	
	Ivy Creek Elementary School	<b>1,583</b>	1,275	308	<b>1,614</b>	1,275	339	<b>1,646</b>	1,275	371	1	
RZR2024-00035	<b>Meadowcreek High School or:</b>	<b>2,521</b>	2,850	-329	<b>2,470</b>	2,850	-380	<b>2,433</b>	2,850	-417	43	
	<b>McClure Health Science High School</b>	<b>1,180</b>	1,500	-320	<b>1,190</b>	1,500	-310	<b>1,200</b>	1,500	-300		
	Lilburn Middle School	<b>1,588</b>	2,000	-412	<b>1,556</b>	2,000	-444	<b>1,542</b>	2,000	-458		33
	Nesbit Elementary School	<b>1,214</b>	1,400	-186	<b>1,202</b>	1,400	-198	<b>1,220</b>	1,400	-180		61
RZR2024-00036	<b>Mill Creek High School</b>	<b>2,721</b>	2,800	-79	<b>2,694</b>	2,800	-106	<b>2,735</b>	2,800	-65	45	
	Osborne Middle School	<b>1,763</b>	1,575	188	<b>1,798</b>	1,575	223	<b>1,816</b>	1,575	241	35	
	Pucketts Mill Elementary School	<b>746</b>	1,200	-454	<b>725</b>	1,200	-475	<b>708</b>	1,200	-492	63	

**Exhibit J: Maps**


**[attached]**







 RZR2024-00032

Created: May 24, 2024







 RZR2024-00032


Created: May 24, 2024

N

0 300 600  
Feet

**SUBJECT SITE AND SURROUNDING ZONING**





 RZR2024-00032

Created: May 24, 2024

 N

 0 300 600 Feet

**2045 UNIFIED PLAN FUTURE DEVELOPMENT CLASSIFICATION**